150 KVA Transformer Supply and Installation Cost Estimate

S.No.	Particulars	Quantity	Rate	Amount	Remarks
1	150 KVA Distribution Trabsformer	1 Nos			
2	11 Meter Steel Tublar Pole	2 Nos			
3	Transformer Tower Complete Set	1 Set			
4	4+1 Channel Bracket	2 Set			
5	11 KV D.O.Fuse Complete Set	1 Set			
6	9 KV Lighting Arrestor	1 Set			
7	11 KV Pin Insulator	9 Set			
8	11 KV PG Clamp	9 Set			
9	11 KV XLPE 3 Core H.T. Cable	83 Mtr			Not in Scale
10	11 KV XLPE Cable Head Jointing Kit Complete Set	2 Set			
11	200 Amp MCCB with Cupper Bus bar Meter Box	1 Nos			
12	240 Sq mm LT Cable	10 Mtr			
13	Copper Earthing Complete Set	3 Set			
14	10 Core Cable	2 Mtr			
15	Different Size of Cable Socket	25 Pcs			
16	11 KV HT Tape	6 Roll			
17	11 KV Insulated Cable	30 Mtr			
18	4" HDPE Pipe	60 Mtr			
19	3" GI Pipe	1 Nos			
					If Add Require
					If Add Require
					If Add Require
					If Add Require
					If Add Require
					If Add Require
					If Add Require
			Sub Total		
			Lab Cost		
			Testing & Communication Charge		
			Total		
			13 % Vat		
			Grand Total		
20	NEA Office Charge				
1	TOD Meter, HT Shu Down, New connection Charge Etc(As per NEA Bill)			Paid By Bank	